

Quick Headwall

Forterra's design team has created another innovative solution designed for speed of installation & versatility. The Forterra Quick Headwall is a precast, engineered unit that is installed in a fraction of the time it would take to utilize a cast-in-place headwall. The unit is designed as a two-piece system complete with chute blocks which utilize standard lifting devices so installation is a breeze. It is the perfect solution for stormwater outlet and stream inlet applications.

Because the Quick Headwall is precast in a controlled environment, it is certified by the Plant Prequalification Program which ensures consistent quality. That coupled with the speed of installation means that projects can be completed sooner and hassle-free!

Benefits of Quick Headwall

- Quick and easy to install.
- Two-piece system complete with chute blocks
- No mechanical fasteners required, no extra site work to be done
- Utilizes standard lifting devices for ease of handling
- Complete with gasket pipe joint- no mortaring of pipe on exposed face OPSD 980.101
- Engineered system designed to CHBDC requirements
- Base rests on granular compacted bed
- Reduction in construction cost due to speed of installation
- Complete with grate OPSD 804.05



**EASY TO
INSTALL**



**SUSTAINABLE
PRODUCT**



**MADE TO
OPSD**



QUICK HEADWALL - TOP SECTION

Pipe Size	A	B	C	D	Wt (kg)	Swift Life (4)
600-825	1702	1429	2938	3302	6,718	4 tonne
900-1200	2006	1829	3242	3302	8,065	4 tonne
1350-1800	2616	2483	3852	3302	10,660	4 tonne

QUICK HEADWALL - BASE SECTION

Pipe Size	E	F	G	Wt (kg)	Swift Life (4)
600-825	3531	3797	2113	8,535	4 tonne
900-1200	3839	3707	2418	9,020	4 tonne
1350-1800	4448	3797	3027	9,990	4 tonne